



NOTES:

1. WIDTH OF RUBBLE INSTALLATION MUST BE 2' BEYOND EDGE OF PIPE WALL.
2. ALL CONSTRUCTION MUST BE IN ACCORDANCE WITH PLAN SPECIFICATIONS, AND FDOT STANDARD SPECIFICATIONS SECTION 985.
3. CONTRACTOR IS WARNED TO COORDINATE THE EXACT LOCATION OF ANY EXISTING UTILITIES WITH THE APPROPRIATE UTILITY COMPANY PRIOR TO ANY CONSTRUCTION EFFORT.
4. ANY MONUMENTS AND PROPERTY CORNERS WITHIN THE LIMITS OF CONSTRUCTION SHALL BE PROTECTED.
5. CONTRACTOR MUST EXERCISE CAUTION IN WORKING NEAR PRIVATE PROPERTY. ANY PROPERTY DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED OR RESTORED TO ORIGINAL CONDITION AT THE CONTRACTORS EXPENSE.
6. ANY EXCESS EXCAVATED MATERIAL WILL BE DISPOSED OF BY DIRECTION OF THE DISTRICT ENGINEER.

(N.T.S.)

RUBBLE ROCK FOR OUTFALL



**MELBOURNE-TILLMAN
WATER CONTROL DISTRICT**

6880 MINTON ROAD
PALM BAY, FL 32907

DRAINAGE DETAIL

D-01

DATE: MAY 2021

APPROVED: _____